Addendum No. 1

RFB No:	PK-HESCO-CON (AIS) KHIPRO GS & NEW T/LINE-NCB/07
Description	Design, Supply, Installation, Testing and Commissioning for Conversion of existing 66 kV Grid Station Khipro into a 132 kV AIS (Air-Insulated Substation) Grid Station, including installation of one (01) 20/26 MVA Power Transformer, along with the associated 132 kV feeding transmission line from 132 KV Kandiari Grid Station.

This Addendum is being issued on 01-7-26 to amend the Request for Bids (RFB) for the above-referenced tender. The Addendum shall form an integral part of the Bidding Documents and shall be complied with by all bidders.

RFB Ref	Previous Clause		Revised Clause	
	Item No.	Description	Item No.	Description
Schedule No. 01. Plant and Mandatory Equipment Supplied (Lot-I)	A	132 kV AIS Switchgear, Equipment.	A	132 kV AIS Switchgear, Equipment.
	1	**132/11.5 kV, 20/26 MVA Power Transformer,** 3 sec, 50 Hz, 10% Impedance, , Vector Group Dyn11, having minimum creepage distance 31mm/kV Bushings, on-load tap-changer (MR Germany make), Terminal connectors for HV & LV Bushing (HV Connectors shall be compatible to Hawthorn Conductor) and all other allied accessories including 11KV LV Bus Bar with all allied hardware for 3Nos 1000MCM Power Cable on each phase , complete in all respect, as per WAPDA/NTDC Specs P-46:2022 (amended to date). Note: Auxiliary Panel of Power Transformer equipped with all allied accessories Complete in all respect shall be provided by the Transformer Manufacturer and shall be included in the Price of the Transformer.	1	**132/11.5 kV, 20/26 MVA Power Transformer,** 3 sec, 50 Hz, 10% Impedance, , Vector Group Dyn11, having minimum creepage distance 31mm/kV Bushings, on-load tap-changer, Terminal connectors for HV & LV Bushing (HV Connectors shall be compatible to Hawthorn Conductor) and all other allied accessories including 11KV LV Bus Bar with all allied hardware for 3Nos 1000MCM Power Cable on each phase , complete in all respect, **as per WAPDA/NTDC (NGC) Specs P-46:2022 (amended to date).** Note: Auxiliary Panel of Power Transformer equipped with all allied accessories Complete in all respect shall be provided by the Transformer Manufacturer and shall be included in the Price of the Transformer.
Schedule No. 03. Installation and Other Services (Lot-I)	A	132 kV AIS Switchgear, Equipment	A	132 kV AIS Switchgear, Equipment
	1	**Installation, Testing & Commissioning of 132/11.5 kV, 20/26 MVA Power Transformer,** 3 sec, 50 Hz, 10% Impedance, Vector Group Dyn11, having minimum creepage distance 31mm/kV Bushings, on-load tap-changer (MR Germany make) and all other allied accessories including 11KV LV Bus Bar with all allied hardware for 3Nos 1000MCM Power Cable on each phase, dehydration, complete work in all respect as per WAPDA/NTDC specifications.	1	**Installation, Testing & Commissioning of 132/11.5 kV, 20/26 MVA Power Transformer,** 3 sec, 50 Hz, 10% Impedance, Vector Group Dyn11, having minimum creepage distance 31mm/kV Bushings, on-load tap-changer, and all other allied accessories including 11KV LV Bus Bar with all allied hardware for 3Nos 1000MCM Power Cable on each phase, dehydration, complete work in all respect as per WAPDA/NTDC **(NGC)** specifications **P-46:2022 (amended to date)**..
Section II – Bid Data Sheet (BDS)		The text in ITB 20.3(a, b & c) is replaced as follows;		The text in ITB 20.3(a, b & c) is replaced as follows;

CamScanner

ITB 20.3(d)		a. An unconditional guarantee issued by a Bank whereas guarantee from non-banking financial institution such as insurance, bonding or Surety Company is not acceptable. If an unconditional guarantee is issued by a bank located outside the Employer's Country, the issuing bank shall have a correspondent bank located in the Employer's Country to make it enforceable. b. Deleted c. Deleted		a. An unconditional guarantee issued by a Bank whereas guarantee from non-banking financial institutions such as insurance, bonding or Surety Company is not acceptable. If an unconditional guarantee is issued by a bank located outside the Employer's Country, the issuing bank shall have a correspondent bank located in the Employer's Country to make it enforceable. b. Deleted c. a cashier's or certified cheque

Note:

All other terms and conditions of the Standard Procurement Documents and Specific Procurement Notice shall remain the same.

17/26

Chief Engineer (Development)
PMU HESCO Hyderabad

CamScanner